

BRUHATH BANGALORE MAHANAGARA PALIKE
YELAHANKA Zone, Kodigehalli Sub Division

DETAILED ESTIMATE FOR Annual maintenance using tractor and men in ward no. 08 Kodigehalli

Ward No. 8

Est. Cost Rs. : 2000000.00

Sl. No.	Description	Unit	Dimensions				Qty.	Rate (Rs.)	Amount (Rs.)
			No.	L	B	D			
1	Engaging Casual Labours (Unskilled mazdoor Heavy) (PWD SR 2018-19, Sl. No. 5, Page No. LVI)								
			months	Av. Days	No.				
	For 12 months at 8 mazdoors on Govt working days average	No.	12	24.00	8.00		2304.00		
							2304.00	446.20	1028045.00
2	1023 - Hire Charges of Tractor 40 HP including Operator and Fuel (P. XLVIII / I. 19, PWD SR 2018-19)								
	For 12 months on each day	Days	12	24.00			288.00		
							288.00	1288.00	370944.00
3	1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XLVIII / I. 23, PWD SR 2018-19)								
	24 hours in a month	Hour	12	24.00			288.00		
	Rs. 5695 per day						288.00	711.87	205019.00
	Rs. 711.87 per hour								
4	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, machining mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Approved data rate enclosed)								
	for broken and missing slabs	Sqm	40	0.60	0.90		21.60	2200.00	47520.00
5	Providing 20 cm thick RCC 1:1.5:3 precast slabs (Approved data rate enclosed)								
	Replacing broken deck slabs	Sqm	28	0.60	1.50		25.20	5300.00	133560.00
	Sub-Total								1785088.00
	Add GST charges at 12%								214211.00
	Miscellaneous & Rounding off								701.00
									2000000.00

TECHNICAL SANCTION

Accorded For Rs. 20.00 lakhs only

Head of A/C P.M. & P.W. works

Div. Ref. No. 23/2021 Date 24/4/2020

CERTIFICATE:

- The work spot has been inspected and the work is found necessary.
- This estimate is prepared as per P.W.D S.R. of 2018-19
- The provisions were made in this estimate are necessary and adequate.
- This works come under B.B.M.P. limits.
- This work has not been taken previously under any other grant.

Assistant Engineer
Ward no. 8
Kodigehalli

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP

Executive Engineer
Byatrayanapura Division
BBMP

Administrative Approval

Accorded For 20.00 lakhs

Head of A/C P-1771

CER NO : 216/192 Dt: 27-03-20

TA

CE (YNK)

KA ZONE
DURGAMCHALLI

Total Population: 8072

Male	4036
Female	4036
Children	1000
Adults	7072
Population Density	778.24

Total Area: 10.50 Ha

Area	10.50
Area	10.50
Area	10.50
Area	10.50
Area	10.50

Total Length of Roads: 10.50 Km

Length	10.50
Length	10.50
Length	10.50
Length	10.50
Length	10.50

Total Length of Footpaths: 10.50 Km

Length	10.50
Length	10.50
Length	10.50
Length	10.50
Length	10.50

[illegible]

Legend

Total Area: 2.92 sq km

— International Road

— Major Road

— Minor Road

— Railway Track